

**RFB 6000000604**  
**Internet Description**

Project Title: Miller Canal Weir No. 3 Replacement, Collier County, FL

Responses Due: March 20, 2014

Dollar Range: \$1,995,000 - \$2,205,000

SBE Utilization: 25%

Inquiry Period: February 19, 2014 – March 10, 2014

Contract Time: 251 Days to Substantial Completion  
311 Days to Final Completion

Liquidated Damages: \$800 per day to Substantial Completion  
\$400 per day to Final Completion

Pre-Bid Meeting: An **Optional Pre-Bid Conference** will be held on **February 27, 2014 at 10:00 AM**, at the Big Cypress Basin Service Center – Administration Building, in the Naples Stanley Hole Conference Room, 2660 Horseshoe Drive North, Naples, Florida 34104, for all interested respondents. A site visit will immediately follow. Transportation will be the responsibility of interested attendees.

Project Description:

The project includes the construction of a three-barreled, cast-in-place, reinforced concrete box culvert structure with invert elevations of 2.18 ft. (NAVD). The culverts will be gated with stainless steel double-leaf 8' x 8' gates and locally automated operation. The Work also includes the placement of riprap, installation of upstream and downstream stilling wells and staff gauges, construction of a 12' x 22' control building with generator and underground fuel tank, cleanup and realignment of drainage ditches, and demolition of the existing weir structure.